

Andhra Pradesh State FiberNet Limited (APSFL)
RFP for Supply, Installation, Commissioning & Maintenance of OFC and PoP Equipment
Ref. No. - APSFL/ OFC & SS Equipment/227/2017, dated 24/11/2017

Corrigendum - 3, Dated-12/12/2017

Bidders may please note that this Corrigendum document is part of the RFP. The items listed in this Corrigendum will supersede the corresponding clauses in RFP.

S.No	Ref/Section #	Page #	Clause in RFP	Revised Clause
1	4	50	24U Rack: Integrated	42U Rack: Integrated Rack 19" Aluminium 42U 800X1000 Front Perforated Door Rear MS Door Sidepanels with 1/3rd ventilation Bottom Plate Heavy Duty Top Plate Fans Vertical PDU 20-socket IEC (C-13) & 4-socket IEC (C-19) with MCB Adjustable screw legs set of 4 nos. Vertical Cable Manager
2	2	50	FDMS	
			Standard fiber count 24F	
			Universal type i.e. suitable for all type of cable (ADSSOFC, Armoured and metal free cable)	Fiber Tray should have the capacity to hold 36 fiber slices and capable of enhancing up to 48 slices
			Dimensions	
			Length-600mm	Fiber tray should be of suitable size to accommodate the above requirement
			Width-375mm	
			Height-175mm	
			Cable entry port-6	Cable entry port-4
Suitable for cable size upto-38mm	Suitable for cable size - 12 to 15 mm			
3	6	51	3KVA UPS with 4 hrs. backup	3KVA UPS with 4 hr backup, along with Isolation Transformer. The isolation transformer must have the below additional features: - Operating Range: 200V-350V - Step Down: -100:90

				- Two earth pits to be provided as per electrical standards
4	7	52	5 KVA UPS with 4 hrs. backup	5KVA UPS with 4 hr backup, along with Isolation Transformer. The isolation transformer must have the below additional features: - Operating Range: 200V-350V - Step Down: -100:90 - Two earth pits to be provided as per electrical standards
5	6(Corrigendum 1)	2	In case of OFC, the selected vendor is responsible only for Supply & Installation. Maintenance of the same shall be done by APSFL appointed O&M vendor for Fiber Grid.	In case of OFC, the selected vendor is responsible for Supply & Installation as well as Maintenance for one year. Subsequent Maintenance of the same shall be done by APSFL appointed O&M vendor for Fiber Grid.
6	9(Corrigendum 1)	2	Modular GPON OLT with 16, 32 and 48 Ports based on minimum needs and with at least one additional slot. In case of higher size, bidder has to supply additional rack along with OLT	Modular GPON OLT with 16, 32 and 48 Ports based on minimum needs and with an expansion of at least 16 ports for items in S.No.22, 23 and 48 ports in S.No.25 in the price bid. In case chassis is higher than 6U in size, then the bidder has to supply a 42U rack(as per specs) to accommodate OLT chassis along with UPS.